9

CITY OF CAMBRIDGE • EXECUTIVE DEPARTMENT

Robert W. Healy, City Manager *Richard C. Rossi, Deputy City Manager*

January 27, 2003

To the Honorable, the City Council:

In response to Awaiting Report #03-09 regarding a report on water not properly draining at the intersection of Pleasant Street and Putnam Avenue, Public Works Commissioner Lisa Peterson reports the following:

At the intersection of Putnam Avenue and Pleasant Street, curb extensions were installed as a traffic calming measure. Three (3) catch basins were also installed to accommodate the surface runoff related to the revamped curbing locations. Catch basin grades and curbing reveals have since been modified to correct the drainage problems that were prevalent at these locations. At the southwest corner, (near the Church) it has been determined that an additional catch basin is needed to rectify the drainage problem there. The City will install an additional catch basin at this location, once the other contractors working at this intersection are complete and before the area is paved. All work at this intersection should be completed in the Spring, 2003.

Very truly yours,

Robert W. Healy
City Manager

795 Massachusetts Avenue, Cambridge, Massachusetts 02139
Voice: 617.349.4300 Fax: 617.349.4307 TTY: 617.349.4242 Web: www.ci.cambridge.ma.us

S-29

Consent Agenda #9

Awaiting Report Item Number 03-09, regarding a report on water not properly draining at the intersection of Pleasant Street and Putnam Avenue.

In City Council January 27, 2003

PLACED ON FILE.